



Agriculture  
Canada

Research  
Branch

Direction générale  
de la recherche

Technical Bulletin 1985-6E

# Haldimand-Norfolk soil survey: pedotechnical interpretations



630.72  
C759  
C 85-6  
c. 3

Canada

The map on the cover has dots representing  
Agriculture Canada research establishments.

# Haldimand-Norfolk soil survey: pedotechnical interpretations

G. WILSON  
Land Resource Research Institute  
Ottawa, Ontario

LRRI Contribution No. 84-57

---

Research Branch  
Agriculture Canada  
1985

Copies of this publication are available from:  
G. Wilson  
Land Resource Research Institute  
Research Branch, Agriculture Canada  
Ottawa, Ontario  
K1A 0C6

Produced by Research Program Service

© Minister of Supply and Services Canada 1985  
Cat. No. A54-8/1985-6E  
ISBN 0-662-14378-7

|  | Page |
|--|------|
| CONTENTS   | iii  |
| PREFACE  | v    |
| ACKNOWLEDGEMENTS   | vi   |
| INTRODUCTION   | 1    |
| NATURE OF SOILS INFORMATION  | 1    |
| KEY TO LANDSCAPE INTERPRETATIONS   | 2    |
| EXAMPLE ILLUSTRATING LANDSCAPE INTERPRETATIONS   | 5    |
| APPLICATION OF SOIL INFORMATION  | 11   |
| Land Factor Ratings  | 12   |
| Guidelines Used in the Rating Scheme   | 17   |
| KEY TO LAND USE INTERPRETATIONS  | 22   |
| EXAMPLE ILLUSTRATING LAND USE INTERPRETATIONS  | 27   |
| HOW TO USE THIS PUBLICATION  | 28   |
| LITERATURE CITED   | 30   |
| APPENDIX I   Detailed Landscape interpretations:<br>Setting sheets for:<br>(a) LIC (Lincoln)   ≈ soils on clay<br>(b) FOX (Fox)       ≈ soils on sand<br>(c) BRT (Brant)     ≈ soils on silt |      |
| APPENDIX II   Detailed Landuse interpretations<br>Land factor ratings for:<br>(a) Soils as construction materials<br>(b) Septic tanks and soil pollution<br>(c) Soil problems and dwellings  |      |

LIST OF TABLES AND FIGURES

Table 1. Key to Landscape Interpretations

Table 2. Landscape Setting Legends

Table 3. Land Factor Ratings

Table 4. Key to Landuse Interpretations (GENERAL)

Table 5. Key to Landuse Interpretations (DETAILED)

Figure 1. Key to Setting Sheet

Figure 2. Septic Tank Interpretation Sheet (Depth of Soil Filter, D)

## PREFACE

A soil survey of the Ontario Regional Municipality of Haldimand-Norfolk has recently been completed and published as Report No. 57. Soil surveys describe the pedological aspect of soils and their application to agriculture and other land uses. Engineers and planners also make use of soil survey information. The publication is complementary to the Haldimand-Norfolk soil survey report. Graphic illustrations are provided to supplement the written descriptions given in the report. It is presumed that engineering users of soil surveys require information about the landscape and its soil characteristics. The term pedotechnical defines this special use and the object of this publication is to encourage more effective use of soil surveys by these professionals.

## PREFACE

Des travaux de prospection pédologique ont pris fin récemment dans la municipalité régionale de Haldiman-Norfolk, en Ontario, et ont été publiés dans le rapport n° 57. Ils décrivent les aspects pédologiques des sols et leur application en agriculture et à d'autres usages. Des ingénieurs et des planificateurs utilisent aussi à ces fins les données de la prospection pédologique. Cette publication complète le rapport sur les travaux de prospection à Haldimand-Norfolk. Ces graphiques illustrent les descriptions présentées dans le rapport. On a supposé que les spécialistes utilisant la prospection pédologique désirent avoir des informations sur le paysage et sur ses caractéristiques pédologiques. Le terme pédotechnique définit cet emploi particulier, et la présente publication a pour but de favoriser une meilleure utilisation des données de prospection par ces spécialistes.

## ACKNOWLEDGEMENTS:

I would like to thank the many people who have cooperated in this work including the soils, secretarial and cartographic staff of the Land Resource Research Institute and the Ontario Institute of Pedology. Special thanks are given to Mr. E. Presant, Ontario Institute of Pedology.

## INTRODUCTION

This publication concerns interpretations for the recently completed Haldimand-Norfolk Soil survey (Presant et al. 1984). It has been customary for many years to include "engineering sections or interpretations" with Canadian soil survey reports (Pawluk, 1968) and to encourage more effective use by planners and engineers (civil as well as agricultural). In response to requests by the Expert Committee on Soil Survey for improved interpretation methodology, pedotechnical interpretations were proposed. The following demonstrates the application of this approach to a very extensive modern survey.

## NATURE OF THE INFORMATION:

A great deal of information is obtained during soil survey and most of it is contained somewhere in the soils report. For reference purposes a requirement exists for better presentation for ready use. This is done in the first instance by separating general information from the detailed. The occasional user may choose to refer only to the general information. For engineering users these terms may also have a different meaning and it is necessary to emphasize that detailed refers to detailed descriptions of (generalized) mapping units. The information usually does not apply to specific sites within any map unit - site information must be obtained separately and in addition to the mapping for specific site applications.

For interpretation purposes a requirement to separately illustrate the type of information needed by engineers as contrasted to planners is recognized. For the former, LANDSCAPE interpretation are provided on the premise that information concerning the landscape and its soil characteristics is required. Access to this information is provided by keys to the map and examples of use.

For planners, LAND USE interpretations are provided on the premise that information concerning the application of soil information to land use planning is the most pressing need. Keys to the map and examples of use are separately given.

#### KEY TO LANDSCAPE INTERPRETATIONS

This key is to help engineering readers make use of the soils map and report to develop a better understanding of the lie of the land. It consists of a number of tables. Listed alphabetically in the first column of Table 1 are the major map unit component symbols of the map units used in the Haldimand-Norfolk soil survey. The 2nd and 3rd column refer the reader to the general and detailed information respectively. The general information is all given on a single page (Table 2) termed "Landscape setting legends", where each of these map unit components is illustrated. This information is complementary to the general legend of the soil survey map.

The third column of Table 1, refers the user to the detailed information on the pedotechnical settings (Appendix 1). The settings illustrate as closely as possible, the concepts of the central theme of the map unit components. The data does not refer to any particular site nor to modal sites within any delineation, although information may have been obtained from specific sites considered to be typical for the map unit component. Most of these map unit components represent soil series.

#### EXAMPLE ILLUSTRATING LANDSCAPE INTERPRETATIONS:

##### (a) General interpretations:

If the symbol LIC occurs in any delineation on the soils map, it infers that the most prevalent soils in that area are likely to be those which are best described by the LIC map unit component. Table 1 lists this map unit component, (LIC refers to the Lincoln soil series) as being illustrated in Legend I on the Landscape Setting Legends (Table 2). Legend I of Table 2 shows that LIC soils illustrated as D on the cross-section diagram, are typical of the poorly drained (P) member of the "D" catena\* of soils (SHV, HIM and LIC).

---


\* Catena - a non taxonomic grouping of a sequence of soils of about the same age, derived from similar parent materials, and occurring under similar climatic conditions, but having unlike characteristics because of variations in relief and in drainage (from AG. CANADA "Glossary of Soil Science terms").

# KEY TO LANDSCAPE INTERPRETATIONS

| MAP<br>UNIT<br>COMPONENT | LANDSCAPE<br>SETTING<br>LEGEND<br><br>(Table 2) | PEDOTECHNICAL<br>SETTING<br>SHEET<br><br>(Appendix 1) |
|--------------------------|---|---|
| ALU                      | VII   | ALU   |
| BAY                      | II  | FOX   |
| BFO                      | I   | BFO   |
| BOO                      | V   | BOO   |
| BOO.T                    | IV  | BOO.T   |
| BOK                      | VI  | FRM   |
| BRR                      | V   | BOO   |
| BRR.H                    | V   | BRR.H   |
| BRR.T                    | IV  | BOO.T   |
| BRT                      | I   | BRT   |
| BUF                      | III   | BUF   |
| BVY                      | I   | BFO   |
| CWO                      | I   | BRT   |
| FOX                      | II  | FOX   |
| FRM                      | VI  | FRM   |
| GNV                      | II  | FOX   |
| GOB                      | IV  | MUI   |
| HIM                      | I   | SHV   |
| HMP                      | VIII  | SYX   |
| KVN                      | IV  | MUI   |
| LDL                      | VIII  | SYX   |
| LIC                      | I   | SHV   |
| LOW                      | II  | LOW   |
| MPW                      | I   | TVK   |
| MUI                      | IV  | MUI   |

| MAP<br>UNIT<br>COMPONENT | LANDSCAPE<br>SETTING<br>LEGEND<br><br>(Table 2) | PEDOTECHNICAL<br>SETTING<br>SHEET<br><br>(Appendix 1) |
|--------------------------|---|---|
| NDE                      | II  | WAT   |
| NGR                      | IV  | OTI   |
| OKL                      | III   | STD   |
| OTI                      | IV  | OTI   |
| OVW                      | VIII  | SYX   |
| PFD                      | II  | PFD   |
| PFD.D                    | II  | PFD   |
| SHV                      | I   | SHV   |
| SIH                      | V   | WSH   |
| SLI                      | II  | WAT   |
| SNA                      | III   | SNA   |
| STD                      | III   | STD   |
| SYX                      | VIII  | SYX   |
| TVK                      | I   | TVK   |
| TLD                      | I   | BFO   |
| TUC                      | I   | BRT   |
| VIT                      | V   | WSH   |
| VSS                      | III   | STD   |
| WAM                      | II  | PFD   |
| WAT                      | II  | WAT   |
| WIL                      | III   | WIL   |
| WLL                      | IV  | OTI   |
| WRN                      | II  | PFD   |
| WSH                      | V   | WSH   |
| WUS                      | V   | BOO   |

# LANDSCAPE SETTING LEGENDS



The cross-section indicates that this "D" catena of soils comes under the general heading of soils on silts and clays. The D soils have developed on the clay section of this silt-clay landscape sequence. The clays are deep, generally more than 10 meters thick (+10m), typically found on the Haldimand plain north of Lake Erie. The cross-section also shows that this catena of soils merges with soils of the "C" catena (BFO, BVY, TLD) which usually occurs at higher elevations further from the lake, and which have siltier textures; and also with the "A" catena (BRT, TUC, CWO) which has developed on the still coarser, deep silty soils occurring at somewhat higher elevations. It should be noted that the "B" catena constitutes an "overlay" soil where the silts are only between 0.4 and 1 m in thickness over clays. No well drained member was mapped in the "B" catena.

It is possible to use only this general information and make good use of the soil survey map for a variety of purposes. Indeed this is as far as many users may need to go. The soil survey field and laboratory data, however, does provide a considerable amount of additional information. To utilize this more detailed information, reference is then made to the third column of Table 1.

(b) Detailed interpretations:

Referring to Table 1, it is noted that detailed information for the Lincoln (LIC) soils is given in appendix I on P/T setting sheet SHV which applies to all soils in that catena. The standard key to the symbology used on the P/T setting sheets is explained in Pedotechnique (Wilson 1982). But

for the specialist user of this type of information it is possible to illustrate its use more briefly here with the key to the pedotechnical setting sheet (Fig. 1) and also with the example given by the LIC symbol.

Fig. 1 is a blank P/T setting sheet with brief explanatory notes. These notes indicate that the general landscape concept as previously explained, is reproduced as module 1; under the heading "1. LANDSCAPE X-SECTIONS".

Typical soil profiles, landscape position, etc are given in module 2 entitled "2. MAP UNIT COMPONENTS".

The map unit component concepts are further described in terms of grain size distribution, plasticity, etc which are included in module 3, as "3. LAND FACTOR DATA".

Continuing with the previous example; according to Table 1 the detailed interpretation of the LIC map unit component is given on P/T setting sheet SHV (Appendix I). Module 1 on this sheet again shows that the LIC symbol refers to the poorly drained member of the Smithville (SHV) catena and illustrates the general setting on the landscape as described previously.

Module 2 indicates that this poorly drained (P) condition refers to a position on the landscape (2.2) where gleysolic soils (G) developed on flat lying ground as a result of groundwater table conditions (2.3) in which the piezometric level (V) in the Bg soil horizon does not drop more than 0.10 to 0.40 m below the ground surface for most of the year except at mid-summer (the ordinate scale is depth, m; the abscissa is a yearly time scale Jan.

# PEDOTECHNICAL SETTING

# SHEET

map unit components

## 1. LANDSCAPE X-SECTIONS

map symbols as landscape concepts

symbols

## 2. MAP UNIT COMPONENTS

Ex 1 component

2:2 development on landscape

2:1 Soil profile

component as a soil profile concept

PT1

horizonation concept 0-1m (PT1)



PT2

PT Layer concept (below control section) 1-2m (PT2) 2-3m (PT3)

PT3


not used in this survey

## 3. LAND FACTOR DATA




## 2. MAP UNIT COMPONENTS


### Ex 2 component



### Ex 3 component




### 3-6 GRAIN SIZE




### 3-7 TEXTURE

UNIFIED


AASHTO




### 3-4 Soil chemistry



### 3-5 Soil Mineralogy



### 3-8 COMPACTION



EROSION - CORROSION : ©

(J) to Dec. (D)). For the Lincoln soils (LIC), the water table is generally not perched; the piezometric level in the Ckg horizon is somewhat less than it is in the Bg horizon indicating downward movement of ground water throughout the year. The soil profile (2.1) indicates that below the cultivated surface horizon Ap (.20 m thick) there is a gleyed horizon Bg (0.2 m thick), and the parent material horizon Ckg is also gleyed.

The grain size distribution curve, (Module 3.6), shows the Bg and Ckg horizons to be similar, with clay contents around 60% which classify the texture of the soil as clayey or very fine, (Module 3.7).

The index properties shown on Module 3.1 indicate the Ckg horizon to be clay of low plasticity, but with high plasticity characteristics in the Bg horizon (LL 50%); shrinkage limit (SL) just below the PL indicating non-elastic parent material soils; porosity is 35%. Combining this plasticity data with the grain size curves exhibited, and using interpretation sheets (Wilson 1982), the C horizon soils have been classified in the range of CL (Unified) and A-7-6(12) (AASHTO) in Module 3.7. Compaction characteristics (Module 3.8) are normal for silty clay, with CBR ( $\gamma_d$ ) values of 1.5 at optimum water content of 27%. The moisture availability is not high (Module 3.2), with 10% available between field capacity (1/10 bar) and wilting point (15 bar). Hydraulic conductivity (K) is very low at less than  $1 \times 10^{-6}$  cm/sec, although infiltration rates (I) have not been measured.

This method of presenting soil survey information sets the stage for its use by other interest groups. A recent example involved specialists concerned with the soil moisture and farm equipment operation. Combining the index, water regime and climatic data the soil moisture analogues and dates for the ground being trafficable 80% of the time were compiled. The method is described, Dyer 1984 and 1985. The analogues are presented on Module 2; the trafficability probability dates (by the arrows) and the soil moisture (by the dotted lines).

#### APPLICATION OF SOILS INFORMATION

For planning, engineering and other non-biological applications of soil survey, interpretations are normally made for land use purposes, (Soil Survey Staff, 1975). For every project involving a change of land use, the value of prime agricultural land should be considered as a first priority. This does not necessarily imply safeguarding individual cultivated areas but rather maintaining the integrity of larger regions well-suited for commercial agriculture. The Haldimand-Norfolk soil report discusses agricultural interpretations which include land capability and crop suitability ratings. These can be used as a guide to the impact of projects involving land use changes. Other engineering land use interpretations are given below. They include interpretations for land use changes associated with such activities as the extraction of material for construction purposes and the use of the land for building site development. The method used in developing ratings with these interpretations is adopted from procedures

described by Marshall et al. (1979) for agricultural capability. However the intent is quite different and instead of referring to capability, the procedure is termed Land Factor Ratings".

#### Land Factor Ratings

A major difference of land factor rating from capability rating is that the pedotechnical scheme refers only to specific land factors important for the use considered, whereas capability for agriculture is a comprehensive rating of the land for general agriculture. In considering the suitability for the land for septic tanks for example, the soil survey information could be used for a basic classification because most factors controlling biological filtration in the soil are already encompassed in agricultural capability ratings. But official ratings of the land for the use of septic tank effluent disposal may also require consideration of certain other factors not fully encompassed during the soil survey operations. (eg. the geo-hydrological conditions of specific areas).

Classes and subclasses are used in the land factor rating system as discussed below:

#### Classes

The classification scheme is comprised of seven (7) classes according to the likelihood of encountering problems (limitations) for the uses being considered. These seven classes provide the user with information about the degree and kind of limitation for broad planning purposes and for assessment

of mitigation measures. These classes are:

Class U1: Land having factors indicative of UNLIKELY soil problems for the use considered.

Classes P2 to P4: Land having factors indicative of POSSIBLE soil problems for the use considered.

Classes L5 to L7: Land having factors indicative of LIKELY soil problems for the use considered.

#### Subclasses

Subclasses are divisions within classes having similar kinds of limitations or problems. These define the land factor problems for the use.

The list of subclasses given below applies to two interpretations which have been made for this report, namely septic tank absorption fields, and dwelling sites. A third interpretation, location of construction materials, follows this discussion.

#### Septic Tank Interpretation:

Subclasses Ds - Stony ground affecting tile trench excavation;  
stoniness above 1m.

Ds' - Stoniness at surface

- Dr - Depth to bedrock or hardpan; depth between 1 to 2m.
- Dr' - At surface (to 1m)
- Dc - Depth to impervious layer; impervious layer between 1 to 2m
- Dc' - Impervious layer at surface (to 1m)
- Dw - Depth to water table;  
water table between 1 and 2m
- Dw' - Water table at surface (to 1m)
- Nn - Nitrogen attenuation problems due to highly pervious layer between 1 & 2m.
- Nn' - Highly pervious layer at surface (to 1m).
- Np - Phosphorus retention problems due to lack of fixation sites between 1 and 2 m.
- Np' - Inadequate fixation near surface (to 1m).
- Ss - Unfavourable land slopes  
Class E slopes: (9-15%)
- Ss' - Slopes above Class E (and Class "A" depressional)
- Si - Pollution hazard due to inundation by overland flow or very poorly drained soil
- Si' - In predicted floodplain area.

Dwellings Interpretation:

- Subclass Es - Stones interfering with excavation; stones at less than 1m
- Es' - Stones at surface
- Er - Excavation problems;  
Bedrock (or hardpan) between 1 & 2m
- Er' - At less than 1m
- Ew - Wet excavation problems; unstable soils between 1 & 2m
- Ew' - At less than 1m
- Fb - Flooding basement hazard; wet pervious zone,  
between 1 & 2m
- Fb' - At less than 1m
- Fi - Inundation of land;  
by overland flow (very poorly drained)
- Fi' - Within floodplain
- Hf - Hazard due to frost heave; susceptible soils  
between 1 & 2m
- Hf' - From surface to 1m
- Hc - Hazard due to swelling clays; susceptible soils  
from surface to 2m
- Hc' - From 2 to 3m
- Hr - Hazard due to expansive rock; susceptible rock  
between 1 & 2m

- Hr' - From surface to 1m
- Sb - Hazard due to differential settlement; weak soil within 4m
- Sb' - Very weak soils within 4m
- So - Hazard due to organic soil subsidence; soils with peaty phases
- So' - Organic soils
- St - Hazard due to soil shrinkage; borderline soils within 4m
- St' - Shrinkable soils within 4m

#### Construction Materials Interpretation:

A similar procedure can be used to indicate the "potential of a soil for a use" rather than limitations for a use. This was done for interpreting the suitability of various soils for construction materials. In this instance the land factor classes are defined as follows:

Class UI : Unlikely potential for location of construction materials.

Classes P2 to P4 : Possible potential for location of construction materials.

Classes L5 to L7 : Likely potential for location of construction materials.

|            |   |   |
|------------|---|---|
| Subclass F | - | Potential sources of roadfill; thickness more than 1m (with less than 1m overburden);   |
| F'         | - | More than 2m in thickness   |
| G or S     | - | Potential sources of sand(S) or gravel (G); more than 1m (with less than 1m overburden) |
| S' or G'   | - | More than 2m in thickness   |
| R          | - | Potential sources of rockfill (R); bedrock, with between 1 & 2m overburden              |
| R'         | - | Bedrock, with less than 1m overburden   |

#### Guidelines Used in the Rating Scheme:

The land factor classification is developed for components of soil map units for which the relevant land factors are identified and separated. The pedotechnical setting sheet permits the central concept of the various soil series, soil phases and miscellaneous land units (soil map unit components) to be identified in terms of land factors such as grain size and compaction characteristics of the soil, etc. A number of specific problems to which the land factors relate are identified for each interpretation. Interpretation sheets (Appendix II) illustrate these problems and provide tables to obtain the subclasses, using the setting sheet as the source of information. The subclasses are grouped according to their combined potential or limitation for the particular land use considered.

The example given below is for the septic tank interpretation. The use of the land for disposal of septic tank effluents is seen as a pollution problem and three specific problems are identified. Land factors are grouped according to these basic problems:

I/ Limitations due to depth limits (D) which define the boundaries of the soil as an effective biological filter.

II/ Limitations due to the degree to which the biological filter (soil) is effective for nutrient attenuation (N).

III/ Limitations due to the setting (S) of the mapping unit on the landscape relative to potential pollution hazards.

Interpretation Sheets D, N and S (Appendix II) permit land factor subclasses (as previously listed) to be determined from the setting sheets for each map unit component. For example on interpretation sheet "D", (Fig. 2), it is seen that the problem has been interpreted in terms of the mitigation measures required to correct the deficiency. The extra amount of fill required to bring the land to an acceptable standard for this land use, provides a rating in quantitative terms. For the 'D' sheet these ratings are:

UNLIKELY - no extra fill required;

POSSIBLE - up to 1m of fill required;


LIKELY - more than 1m of fill required.

# INTERPRETATION

## SEPTIC TANKS

# SOIL PROBLEMS DUE TO

## DEPTH OF SOIL FILTER, D



### PROBLEM

Extra Filter (z) Required

### FACTORS CONSIDERED





Depth to Bedrock (and hardpan) ————— Dr  
 Presence of Stones ————— Ds  
 Depth to Impervious Layer ————— Dc  
 Depth to Water Table ————— Dw

### STONES

BEDROCK  
(or hardpan)

### DEPTH TO IMPERVIOUS LAYER

### DEPTH TO WATER TABLE



### INTERPRETATION

| PROBLEM CLASS | STONES in PT1 layer |     | BEDROCK AND HARDPAN |     | IMPERVIOUS LAYER |     | WATER TABLE      |     |
|---------------|---------------------|-----|---------------------|-----|------------------|-----|------------------|-----|
|               |                     |     |                     |     |                  |     |                  |     |
| UNLIKELY      | below PT1           | —   | below PT2 —         | —   | zone —           | —   | within zone —    | —   |
| POSSIBLE      | at surface only (S) | Ds  | in PT2 only (R)     | Dr  | zone (C)         | Dc  | within zone (W)  | Dw  |
| LIKELY        | in PT1 (S')         | Ds' | in PT1 (R')         | Dr' | within zone (C') | Dc' | within zone (W') | Dw' |

The different land factors contributing to this depth deficiency are listed as the presence of stones (s), the presence of bedrock or hardpan (r), the presence of an impervious layer (c), and the presence of a high water table condition (w). The method of rating is to compare the information on the appropriate module of the setting sheet with that of the interpretation sheet. On the interpretation sheet (D), the column entitled "Depth to impervious layer", shows 3 envelopes; one with the symbol ("C", one with the symbol "C" and another with the symbol "-"). The C' symbol indicates that any soil between the ground surface and a depth of 1m (i.e. the PT 1 layer), which has a K value of  $10^{-4}$  cm/sec or less (i.e. an infiltration rate of less than 0.5 in./hr) is given the LIKELY rating, Dc' for the land factor C (presence of impervious layer at shallow depth). A borderline condition is recognized for soils with infiltration rates between 1" and 0.5 in./hr in the top metre. The borderline (POSSIBLE) rating, Dc is also given for soils with infiltration rates less than 0.5 in./hr but which are between 1m and 2m below the ground surface. For all other conditions the UNLIKELY rating "-" applies.

The soil unit components of the Haldimand-Norfolk Region were classified into seven (7) land factor classes following the procedure described. This provides for a ranking of the map components according to the severity of the problem. The scheme in detail is shown below;

| LAND FACTOR CLASS   | INTERPRETATION   |
|---------------------|--|
| <u>SEPTIC TANKS</u> |  |
| UI                  | - Pollution problems unlikely: mitigation methods should not be required.                              |
| P2                  | - Possible problems due to depth (Ds, Dr, Dc, Dw): mitigation may require < 1m of fill.                |
| P3                  | - Possible problems due to nutrients (Nn, Np); further investigation is required.                      |
| P4                  | - Possible problems due to setting (Ss, Si); mitigation may require design modifications.              |
| L5                  | - Likely problems due to depth (Ds', Dr', Dc', Dw'); mitigation should require > 1m of fill.           |
| L6                  | - Likely problems due to nutrients (Nn', Np'); mitigation should require special construction methods. |
| L7                  | - Likely problems due to setting (Ss', Si'); serious problems not likely to be mitigated.              |

## KEY TO LAND USE INTERPRETATIONS:

The key to general land use interpretations is given on Table 4. It illustrates how the reader can make use of the rating symbols given in Table 3, for interpretation purposes. The LIC map unit component is used for the illustration; the rating for septic tanks for this map unit component is obtained from Table 3 as L5Dc'w' (column 2). The most general interpretation of this symbol, Table 4 is shown to be that pollution problems are LIKELY (L) to result if septic tanks are used on this type of land. This is the most general level of the land use interpretations and it may be as far as many users of this information need to go.

It is possible however, to progress beyond this as shown on Table 5 which provides the key to detailed land use interpretations. The rating L5Dc'w' could also denote that the land factors contributing to this rating are due specifically to the lack of sufficient depth (D) of aerated soil due to the presence at shallow depth of an impervious layer (c') and the water table (w'). It is further implied that the problem could be mitigated, but this could require the addition of more than 1m of pervious fill. Table 3 lists the map unit components and their ratings for the 3 land use changes considered i.e. septic tanks, dwelling sites and extraction of construction materials.

TABLE 3

| PEDOTECHNICAL LAND FACTOR RATINGS |                 |          |               |                   |                           |
|-----------------------------------|-----------------|----------|---------------|-------------------|---------------------------|
| MAP UNIT<br>COMPONENT             | SEPTIC<br>TANKS |          |               | DWELLING<br>SITES | CONSTRUCTION<br>MATERIALS |
|                                   | Slope Classes * |          |               | Slope Classes *   |                           |
| ①                                 | Aa to Dd<br>②   | Ee<br>③  | Ff to Gg<br>④ | Aa to Gg<br>⑤     | Aa to Gg<br>⑥             |
| 1 ALU                             | L7.Dw'Si'       | -        | -             | L7.EwFi'Sb        | U1.                       |
| 2 ALU                             | L7.DwNn'Si'     | -        | -             | L7.EwFi'          | P3.FS                     |
| 3 ALU                             | L7.Si'          | -        | -             | L7.Fi'HfSb        | P2.F                      |
| 4 ALU                             | L7.Dc'Si'       | -        | -             | L7.Fi'HfSb        | U1.                       |
| BAY                               | L5.Dw'Nn        | -        | -             | L7.Ew'Fb'Sb       | L6.F'S'                   |
| BFO                               | P2.Dc           | P4.Ss    | L7.Ds'        | P4.HfSb           | U1.                       |
| BOO                               | P2.Dc           | P4.DcSs  | L7.DcSs'      | P4.Sb             | U1.                       |
| BOO.T                             | P2.Dc           | P4.DcSs  | L7.DcSs'      | P4.Sb             | L5.F'                     |
| BOK                               | L5.Dr'          | -        | -             | L5.Er'            | P4.R                      |
| BRR                               | L5.Dc'w'        | -        | -             | L7.HfSbFb'        | U1.                       |
| BRR.H                             | L5.Dc'w'        | -        | -             | L7.EwFb'.Sb       | U1.                       |
| BRR.T                             | L5.Dc'w'        | -        | -             | P4.HfSb           | P2.F                      |
| BRT                               | P2.Dc           | P4.DcSs  | L7.DcSs'      | P4.Sb             | L5.F'                     |
| BUF                               | L6.Nn'          | L6.Nn'Ss | L7.Nn'Ss'     | U1.               | L6.F'G'                   |
| BVY                               | L5.Dw'          | -        | -             | L7.Fb'HfSb        | U1.                       |
| CWO                               | L5.Dcw'         | -        | -             | L7.EwFb'          | P2.F                      |
| FOX                               | P3.Nn           | P4.Ss'   | L7.Ss'        | P4.Sb             | L6.F'S                    |
| FRM                               | L5.Dr'          | L5.Dr'Ss | L7.Dr'Ss'     | L5.Er'            | L7.R'                     |
| GNV                               | L5.Dw'Nn        | -        | -             | L7.Ew'Fb'Sb       | L6.F'S                    |
| GOB                               | L5.Dc'w'        | -        | -             | P4.HfSb           | U1.                       |
| HIM                               | L5.Dc'w'        | -        | -             | P4.HfSb           | U1.                       |
| HMP                               | L7.Si'          | -        | -             | L7.Fi'            | U1.                       |
| KVN                               | L5.Dc'w'        | -        | -             | P4.HfSbFb         | U1.                       |
| LDL                               | L7.Si'          | -        | -             | L7.Fi'            | U1.                       |
| LIC                               | L5.Dc'w'        | -        | -             | P4.HfSb           | U1.                       |
| LOW                               | L6.Dw'Nn'       | -        | -             | L7.Ew'Fb'Sb       | P3.FS                     |
| MPW                               | L5.Dc'w'        | -        | -             | P4.HfSbFb         | U1.                       |

\* See Table 4

TABLE 3(cont.)

| PEDOTECHNICAL LAND FACTOR RATINGS |                 |          |               |                   |                           |
|-----------------------------------|-----------------|----------|---------------|-------------------|---------------------------|
| MAP UNIT<br>COMPONENT             | SEPTIC<br>TANKS |          |               | DWELLING<br>SITES | CONSTRUCTION<br>MATERIALS |
|                                   | Slope Classes * |          |               | Slope Classes *   |                           |
|                                   | Aa to Dd<br>②   | Ee<br>③  | Ff to Gg<br>④ | Aa to Gg<br>⑤     | Aa to Gg<br>⑥             |
| ①                                 |                 |          |               |                   |                           |
| MUI                               | L5.Dc'          | L5.Dc'Ss | L7.Dc'Ss'     | P4.Sb             | U1.                       |
| NDE                               | L5.Dw'Nn        | -        | -             | L7.Ew'Fb'         | L5.F'S                    |
| NGR                               | L5.Dc'w'        | -        | -             | P4.HfSb           | U1.                       |
| OKL                               | L5.Dw'          | -        | -             | P4.HfSb           | L5.F'                     |
| OTI                               | L5.Dc'          | L5.Dc'Ss | L7.Dc'Ss'     | P4.Sb             | U1.                       |
| OVW                               | L7.Si'          | -        | -             | L7.Fi'            | U1.                       |
| PFD                               | P3.Nn           | P4.NnSs  | L7.NnSs'      | P4.Sb             | P3.FS                     |
| PFD.D                             | P3.Nn           | P4.NnSs  | L7.NnSs'      | P4.Sb             | P3.FS                     |
| SHV                               | L5.Dc'          | L5.Dc'Ss | L7.Dc'Ss'     | P4.Sb             | U1.                       |
| SIH                               | L5.Dc'w'        | -        | -             | L7.Ew'HfFb'       | P2.F                      |
| SLI                               | L5.Dw'Nn        | -        | -             | L7.Ew'Fb'         | L5.F'S                    |
| SNA                               | U1.             | P4.DsSs  | L7.DsSs'      | P4.Sb             | P2.F                      |
| SYX                               | L7.Si'          | -        | -             | L7.Fi'            | U1.                       |
| TVK                               | L5.Dc'w'        | -        | -             | P4.HfSb           | U1.                       |
| TLD                               | L5.Dw'          | -        | -             | L7.Fb'HfSb        | U1.                       |
| TUC                               | L5.Dc'w'        | -        | -             | P4.HfSb           | L5.F'                     |
| STD                               | U1.             | P4.DcSs  | L7.DcSs'      | P4.Sb             | L5.F'                     |
| VIT                               | L5.Dc'w'        | -        | -             | L7.Ew'HfFb'       | P2.F                      |
| VSS                               | L5.Dw'          | -        | -             | P4.HfSb           | P2.F                      |
| WAM                               | L5.NnDw'        | -        | -             | L7.Ew'Fb'Sb       | P3.FS                     |
| WAT                               | P3.Nn           | P4.NnSs  | L7.NnSs'      | P4.Sb             | L5.F'S                    |
| WIL                               | P3.Dc           | P4.DcSs  | L7.DcSs'      | U1.               | L5.F'                     |
| WLL                               | L5.Dc'w'        | -        | -             | P4.HfSb           | U1.                       |
| WRN                               | L5.Dw'Nn        | -        | -             | L7.Ew'Fb'Sb       | P3.FS                     |
| WSH                               | L5.Dc'          | L5.Dc'Ss | L7.Dc'Ss'     | P4.Sb             | P2.F                      |
| WUS                               | L5.Dc'w'        | -        | -             | L7.HfFb'          | U1.                       |
| WUS.T                             | L5.Dc'w'        | -        | -             | L7.HfFb'          | P2.F                      |

\* See Table 4

| KEY TO LAND USE INTERPRETATIONS  |   |  |
|--|---|--|
| GENERAL:   |   |  |
| LAND FACTOR RATING   | INTERPRETATION  |  |
| <b>SEPTIC TANKS AND DWELLINGS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____ | } ..... unlikely soil problems<br>} ..... possible soil problems, as detailed (Table 5)<br>} ..... likely soil problems               |  |
| <b>CONSTRUCTION MATERIALS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____     | } ..... unlikely location for resource materials<br>} ..... possible location resource materials (Table 5)<br>} ..... likely location |  |

**\*Note on Slope Classes:**

| Simple                | %                          | Complex               |
|-----------------------|----------------------------|-----------------------|
| A to D<br>E<br>F to G | 0 to 9<br>10 to 15<br>16 + | a to d<br>e<br>f to g |

| KEY TO LAND USE INTERPRETATIONS  |   |  |
|--|---|--|
| GENERAL:   |   |  |
| LAND FACTOR RATING   | INTERPRETATION  |  |
| <b>SEPTIC TANKS AND DWELLINGS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____ | } ..... unlikely soil problems<br>} ..... possible soil problems, as detailed (Table 5)<br>} ..... likely soil problems               |  |
| <b>CONSTRUCTION MATERIALS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____     | } ..... unlikely location for resource materials<br>} ..... possible location resource materials (Table 5)<br>} ..... likely location |  |

**\*Note on Slope Classes:**

| Simple                | %                          | Complex               |
|-----------------------|----------------------------|-----------------------|
| A to D<br>E<br>F to G | 0 to 9<br>10 to 15<br>16 + | a to d<br>e<br>f to g |

| KEY TO LAND USE INTERPRETATIONS  |   |  |
|--|---|--|
| GENERAL:   |   |  |
| LAND FACTOR RATING   | INTERPRETATION  |  |
| <b>SEPTIC TANKS AND DWELLINGS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____ | } ..... unlikely soil problems<br>} ..... possible soil problems, as detailed (Table 5)<br>} ..... likely soil problems               |  |
| <b>CONSTRUCTION MATERIALS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____     | } ..... unlikely location for resource materials<br>} ..... possible location resource materials (Table 5)<br>} ..... likely location |  |

**\*Note on Slope Classes:**

| Simple                | %                          | Complex               |
|-----------------------|----------------------------|-----------------------|
| A to D<br>E<br>F to G | 0 to 9<br>10 to 15<br>16 + | a to d<br>e<br>f to g |

| KEY TO LAND USE INTERPRETATIONS  |   |  |
|--|---|--|
| GENERAL:   |   |  |
| LAND FACTOR RATING   | INTERPRETATION  |  |
| <b>SEPTIC TANKS AND DWELLINGS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____ | } ..... unlikely soil problems<br>} ..... possible soil problems, as detailed (Table 5)<br>} ..... likely soil problems               |  |
| <b>CONSTRUCTION MATERIALS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____     | } ..... unlikely location for resource materials<br>} ..... possible location resource materials (Table 5)<br>} ..... likely location |  |

**\*Note on Slope Classes:**

| Simple                | %                          | Complex               |
|-----------------------|----------------------------|-----------------------|
| A to D<br>E<br>F to G | 0 to 9<br>10 to 15<br>16 + | a to d<br>e<br>f to g |

| KEY TO LAND USE INTERPRETATIONS  |   |  |
|--|---|--|
| GENERAL:   |   |  |
| LAND FACTOR RATING   | INTERPRETATION  |  |
| <b>SEPTIC TANKS AND DWELLINGS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____ | } ..... unlikely soil problems<br>} ..... possible soil problems, as detailed (Table 5)<br>} ..... likely soil problems               |  |
| <b>CONSTRUCTION MATERIALS</b><br><br>U1. _____<br>P2. _____ etc _____<br>P3. _____<br>P4. _____<br>L5. _____<br>L6. _____<br>L7. _____     | } ..... unlikely location for resource materials<br>} ..... possible location resource materials (Table 5)<br>} ..... likely location |  |

**\*Note on Slope Classes:**

| Simple                | %                          | Complex               |
|-----------------------|----------------------------|-----------------------|
| A to D<br>E<br>F to G | 0 to 9<br>10 to 15<br>16 + | a to d<br>e<br>f to g |

| KEY TO LAND USE INTERPRETATIONS   |  |                       |        |   |         |                       |                            |                       |
|---|--|-----------------------|--------|---|---------|-----------------------|----------------------------|-----------------------|
| GENERAL:  |  |                       |        |   |         |                       |                            |                       |
| LAND FACTOR RATING  | INTERPRETATION   |                       |        |   |         |                       |                            |                       |
| <p><b>SEPTIC TANKS AND DWELLINGS</b></p> <p>U1. _____</p> <p>P2. _____ etc _____</p> <p>P3. _____</p> <p>P4. _____</p> <p>L5. _____</p> <p>L6. _____</p> <p>L7. _____</p>   | <p>} ..... unlikely soil problems</p> <p>} ..... possible soil problems, as detailed (Table 5)</p> <p>} ..... likely soil problems</p>               |                       |        |   |         |                       |                            |                       |
| <p><b>CONSTRUCTION MATERIALS</b></p> <p>U1. _____</p> <p>P2. _____ etc _____</p> <p>P3. _____</p> <p>P4. _____</p> <p>L5. _____</p> <p>L6. _____</p> <p>L7. _____</p>   | <p>} ..... unlikely location for resource materials</p> <p>} ..... possible location resource materials (Table 5)</p> <p>} ..... likely location</p> |                       |        |   |         |                       |                            |                       |
| <p><b>*Note on Slope Classes:</b></p> <table border="1"> <thead> <tr> <th>Simple</th> <th>%</th> <th>Complex</th> </tr> </thead> <tbody> <tr> <td>A to D<br/>E<br/>F to G</td> <td>0 to 9<br/>10 to 15<br/>16 +</td> <td>a to d<br/>e<br/>f to g</td> </tr> </tbody> </table> |  |                       | Simple | % | Complex | A to D<br>E<br>F to G | 0 to 9<br>10 to 15<br>16 + | a to d<br>e<br>f to g |
| Simple  | %  | Complex               |        |   |         |                       |                            |                       |
| A to D<br>E<br>F to G   | 0 to 9<br>10 to 15<br>16 +   | a to d<br>e<br>f to g |        |   |         |                       |                            |                       |

TABLE 5

# KEY TO LAND USE INTERPRETATIONS

## DETAILED:

| LAND FACTOR RATING            | INTERPRETATION                         |  |
|-------------------------------|--|--|
| <b>SEPTIC TANKS</b>           | <b>problem</b>                         | <b>detail</b>  |
| U1.                           | —                                      |  |
| P2.DsDcDwDr                   | shallow depth ..... D                  | s - stoney soil                      w - water table<br>c - impervious soil                r - bedrock                                 |
| P3.NnNp                       | nutrient attenuation ..... N           | n - nitrogen                        p - phosphorous  |
| P4.SsSi                       | unfavourable setting ..... S           | s - land slope                      i - inundation   |
| L5.Ds'Dw'Dc'Dr'               | .....                                  | .....  |
| L6.Nn'Np'                     | ..... as above .....                   | ..... as above .....   |
| L7.Ss'Si'                     | .....                                  | .....  |
| <b>DWELLINGS</b>              |  |  |
| U1.                           | —                                      |  |
| P2.EsErEw                     | difficult excavation ..... E           | s - stoney soil                      w - water table<br>r - bedrock  |
| P3.HfHcHr                     | ground heave ..... H                   | f - frost                              r - swelling rock<br>c - swelling clay  |
| P4.SoSbStFbFi                 | settlement ..... S<br>flooding ..... F | o - organic soil                      b - basement flood<br>b - weak soil                        i - inundation<br>t - shrinkable soil |
| L5.Es'Er'Ew'                  | .....                                  | .....  |
| L6.Hf'Hc'Hr'                  | ..... as above .....                   | ..... as above .....   |
| L7.So'Sb'St'Fb'Fi'            | .....                                  | .....  |
| <b>CONSTRUCTION MATERIALS</b> | <b>resource material</b>               |  |
| U1.                           | —                                      |  |
| P2.F                          | roadfill ..... F                       |  |
| P3.SG                         | sand ..... S<br>gravel ..... G         |  |
| P4.R                          | rock ..... R                           |  |
| L5.F'                         | .....                                  |  |
| L6.S'G'                       | ..... as above .....                   |  |
| L7.R'                         | .....                                  |  |

\*see also Guidelines

## EXAMPLE ILLUSTRATING LAND USE INTERPRETATIONS:

If the symbol LIC occurs in any delineation on the soil map, it infers that the most prevalent soils in that area are likely to be those best described by the LIC map unit component. Table 3 gives, for this map unit component, the ratings L5Dc'w', P4HfSb and UI for land use changes due to installation of septic tanks, dwelling sites and extraction of construction materials, respectively. These ratings can be generalized by considering only the first letter i.e. L, P and U. As indicated in Table 4, these symbols can be interpreted as indicating severe pollution problems to be likely (L) if septic tanks were used without strict control at dwelling sites where soil problems (P) could occur, suggesting the land is only moderately suited for this purpose. The land is unlikely to be a resource for construction materials (U). Thus it might be better to leave such land in agriculture since it is generally unsuitable for septic tanks or construction materials. However if dwelling sites were to be seriously considered, it would be advisable to have soils experts report on septic tank waste disposal systems and to carry out tests on the soils, especially the deeper soils, to verify their competence for building foundations.

If two components are included in a map unit e.g. LIC (Lincoln) and FRM (Farmington), in approximate proportions of 70:30, the above remarks would only apply to the soils occupying about 70% of the area. For the remaining 30% of FRM soils, Table 3 (map unit component FRM) would indicate L5, L5 and L7 for the same uses. Similar remarks as given above for the LIC symbol might apply to the use of septic tanks and dwellings for this other type of land, but for different reasons. There could also be possible land use conflicts with quarry operations (L7), but little conflict with agriculture (agricultural capability would only be rated as Class 6).

#### HOW TO USE THIS PUBLICATION

If the reader is only interested in the general role of the Haldimand-Norfolk soils map in planning or for similar regional problems, reference could be made directly to the section explaining the (key to land use interpretations) and to Table 3.

If on the other hand the reader is only interested in obtaining a general appreciation and understanding of the soils in the area, reference could be made directly to the section explaining the (landscape interpretations) and to Table 2. For these purposes it should be noted that the information given applies to the entire area delineated and not to any particular site within these delineations.

Users interested in developing a working knowledge of the soils and an ability to efficiently use the soils map would be advised to consider both

sections of this publication and also to consult the Haldimand-Norfolk soil survey report. Finally it may be said that there are also other survey records, (geological, hydrological, ground water, terrain analysis and others) from provincial, federal and private agencies which should be consulted for a full appreciation of the land resources of this region.

## LITERATURE CITED

Dyer, J.A. and Mack, A.R. 1984. The versatile soil moisture budget - version three. LRRI contribution No. 82-33. Agriculture Canada.

Dyer, J.A. and Murray, D.R. 1985. Planting and harvesting dates in Ontario. OMAF Fact Sheet (in press).

Marshall, I.B., Dumanski, J., Huffman, T., Lajoie, P.G. 1979. "Soils, capability and land use in the Ottawa Urban Fringe". Land Resource Research Institute, Agriculture Canada.

Pawluk, S. 1968. Report of Subcommittee on Soil Survey Interpretations for Engineering purposes. Proc. 8th Meeting Nat. Soil Surv. Committee of Canada. pp. 167-174.

Presant, E.W. and C.J. Acton. 1984. The Soils of the Regional Municipality of Haldimand-Norfolk. Report No. 57 of the Ont. Inst. of Pedology, LRRI contribution No. 84-13.

Soil Survey Staff. 1975. Soil Taxonomy. A Basic System of Soil Classification for Making and Interpreting Soil Survey. U.S. Government Printing Office, Washington, D.C.

USDA. 1971. Guide for Interpreting Engineering Uses of Soils.  
Soil cons. Serv., USDA, Washington, D.C.

Wilson, G. 1982. Pedotechnique and its Application to Soil  
Surveys - A proposal. LRRI Contribution No. 82-12. Agriculture Canada.

Wilson, G. 1983. Interpretation Sheets for Engineering  
Classifications in Soil Surveys. Can. J. Soil Sci. 63: 679-689.

# PEDOTECHNICAL SETTING


# SHEET

*SHV, HIM, LIC*

map unit components

## 1. LANDSCAPE X-SECTIONS

*Soils on Silts & Clays:*



## LEGEND

map unit components

drainage

w P

A BRT TUC CWO

B - TVK MPW

C BFO BVY TLD

D SHV HIM LIC


Silts

Silty clays




Clays

Lake Erie

## 2. MAP UNIT COMPONENTS





## 3. LAND FACTOR DATA



## LEGEND





Legends & scales for all symbols used above

## 2. MAP UNIT COMPONENTS



### 3-7 TEXTURE

| UNIFIED |    | AASHTO    |
|---------|----|-----------|
| ML      | Ap | A-7-6(0)  |
| CH      | Bg | A-7-6(20) |
| CL      | Ck | A-7-6(12) |




EROSION - CORROSION: ©

# PEDOTECHNICAL SETTING FOX, BAY, GNY ---

SHEET  
 map unit  
 components


## 1. LANDSCAPE X-SECTIONS

Soils on Sands






| X-SECTION symbols | LEGEND<br>map unit components |     |     |
|-------------------|-------------------------------|-----|-----|
|                   | drainage                      |     |     |
|                   | W                             | I   | P   |
| E                 | WAT                           | NDE | SLI |
| F                 | FOX                           | BAY | GNY |
| G                 | BFD                           | WAM | WRN |
| H                 | -                             | -   | LOW |
|                   | Sand (m.to.c.)                |     |     |
|                   | fine sandy loam               |     |     |
|                   | sand (f.)                     |     |     |
|                   | loamy fine sand               |     |     |

## 2. MAP UNIT COMPONENTS









## 3. LAND FACTOR DATA



## LEGEND


Legends & scales for all symbols used above.

## 2. MAP UNIT COMPONENTS



map unit  
components

### Soils on Silts & Clays:




map unit  
components

| Stations | drainage             |     |     |
|----------|----------------------|-----|-----|
|          | W                    | I   | P   |
| A        | BRT                  | TUC | CWO |
| B        | -                    | TVK | MPW |
| C        | <sup>NW</sup><br>BFO | BVY | TLD |
| D        | <sup>NW</sup><br>SHV | HIM | LIC |
| ///      | Silts                |     |     |
| ///      | Silty clays          |     |     |
| ///      | clays                |     |     |
| ▽        | Lake Erie            |     |     |

BRT component

## 2.2 development on landscape









The diagram is a chromatogram with a horizontal axis at the bottom labeled from 0 to 100 in increments of 10. Above the axis, several peaks are identified with labels: LS (at ~5%), SL (at ~10%), PL (at ~25%),  $\omega$  (at ~45%), and LL (at ~75%). Below the axis, there are two rows of labels: FME (under PL),  $\eta$  (under  $\omega$ ), FS (under LL), and SE (at ~95%). The chromatogram itself consists of a series of horizontal lines with vertical tick marks representing the baseline and peaks. The peaks are labeled with red ink:  $A_p$  (at ~15%),  $B_g$  (at ~25%),  $C_{kg}$  (at ~45%), and  $NP$  (at ~55%). The text 'INDEX' is written in the top right corner, and '3-1' is written in the top left corner. The text 'PT 2' and 'PT 3' are written on the left side, corresponding to the second and third rows of the chromatogram.

Figure 1 consists of four vertically stacked plots sharing a common x-axis labeled  $I$ . The top plot shows  $\text{Bar}$  (pF) on the y-axis (log scale, 1 to 10) versus  $I$  (pF) on the x-axis (log scale, 40 to 10). A red curve labeled  $A_p$  is shown. The second plot shows  $\theta\%$  on the y-axis (log scale, 1 to 10) versus  $I$  (pF) on the x-axis (log scale, 40 to 10). A red curve is shown. The third plot shows  $K$  (Cms/s) on the y-axis (log scale, 10<sup>5</sup> to 10<sup>3</sup>) versus  $I$  (ins/hr) on the x-axis (log scale, 0.1 to 10). A red curve is shown. The bottom plot shows  $K_{pF2}$  and  $K_{pF0}$  on the y-axis (log scale, 10<sup>5</sup> to 10<sup>3</sup>) versus  $I$  (ins/hr) on the x-axis (log scale, 0.1 to 10). Red curves are shown for both  $K_{pF2}$  and  $K_{pF0}$ .


Legends & scales for all symbols used above:

## 2. MAP UNIT COMPONENTS



## RESOURCE MATERIALS

RESOURCE,




## FACTORS


Thickness  
W/Table  
Texture  
Stones

## TYPE OF MATERIALS


Gravel (or sand) ————— G (S)  
Road Fill ————— F  
Rock Fill ————— R

THICKNESS  
and w/ table

## GRAVEL (or sand)



## ROAD FILL




| RESOURCE CLASS | GRAVEL (and sand)                                   |        | ROAD FILL  |    | ROCK FILL                                   |    |
|----------------|---|--------|--|----|---|----|
| UNLIKELY       | Thickness $\ominus$<br>or<br>Texture $\ominus$      | —      | Thickness $\ominus$<br>or<br>AASHTO $\ominus$      | —  | Rock below PT2                              | —  |
| POSSIBLE       | Thickness $\oplus$<br>Texture $\oplus$ or $\oplus'$ | G(S)   | Thickness $\oplus$<br>AASHTO $\oplus$ or $\oplus'$ | F  | Rock in PT2<br>(limestone, L)<br>(ssine, S) | R  |
| LIKELY         | Thickness $\oplus'$<br>Texture $\oplus'$            | G'(S') | Thickness $\oplus'$<br>AASHTO $\oplus'$            | F' | Rock in PT1<br>(Granite, g)<br>(Shale, h)   | R' |

# INTERPRETATION

## SEPTIC TANKS

# SOIL PROBLEMS DUE TO DEPTH OF SOIL FILTER, D



### PROBLEM

Extra Filter (z) Required

### FACTORS CONSIDERED

Depth to Bedrock (and hardpan) ————  $D_r$   
 Presence of Stones ————  $D_s$   
 Depth to Impervious Layer ————  $D_c$   
 Depth to Water Table ————  $D_w$


### STONES

BEDROCK  
(or hardpan)

### DEPTH TO IMPERVIOUS LAYER

### DEPTH TO WATER TABLE

### WATER REGIME



## INTERPRETATION

| PROBLEM CLASS | STONES<br>in PT1 layer |        | BEDROCK<br>AND HARDPAN |        | IMPERVIOUS<br>LAYER |        | WATER TABLE    |        |
|---------------|------------------------|--------|------------------------|--------|---------------------|--------|----------------|--------|
| UNLIKELY      | below PT1              | —      | below PT2 —            | —      | zone —              | —      | within zone —  | —      |
| POSSIBLE      | at surface<br>only S   | $D_s$  | in PT2 only<br>R       | $D_r$  | zone C              | $D_c$  | within zone W  | $D_w$  |
| LIKELY        | in PT1 S'              | $D_s'$ | in PT1 R'              | $D_r'$ | within zone C'      | $D_c'$ | within zone W' | $D_w'$ |

# INTERPRETATION

## SEPTIC TANKS

## SOIL PROBLEMS DUE TO NUTRIENT ATTENUATION, N


### PROBLEM

Improving Soil as  
a Biological Filter

### IMPROVEMENTS REQUIRED FOR

Denitrification ————— Nn

Phosphorous Retention — Np



### DENITRIFICATION

#### WATER REGIME

K  $10^{-5}$   $10^{-3}$   $\text{cm/s}$




N.B. \* for Well Structured Soils,  
uprate (N) → (N) and  
(N) → (-)

### PHOSPHOROUS RETENTION

#### INDEX

S.E. (%)



S.E. = Sand Equivalent  
K = Hydraulic Conduct.

### INTERPRETATION


| PROBLEM CLASS | DENITRIFICATION<br>(PT1 and PT2 Layers) |     | PHOSPHOROUS RETENTION<br>(PT1 and PT2 Layers) |     |
|---------------|---|-----|---|-----|
| UNLIKELY      | zone (-)                                | -   | zone (-)                                      | -   |
| POSSIBLE      | zone (N) (*adjust for structure)        | Nn  | zone (P)                                      | Np  |
| LIKELY        | zone (N') (*adjust for structure)       | Nn' | zone (P')                                     | Np' |

# INTERPRETATION

## SEPTIC TANKS

## SOIL PROBLEMS DUE TO SETTING AND SLOPE, S

### Inundation



### PROBLEM

danger of pollution  
due to  
unfavourable settings

### SETTINGS CONSIDERED


Inundation ————— Si  
Hydrogeology ————— Sh  
Unfavourable Slopes ——— Ss

### INUNDATION

### HYDROGEOLOGY

### SLOPES


#### Soil Map



#### Overland Flow

Si { v.p. drained  
or  
peaty  
or  
organic soils

#### Geotech Setting



#### Floodplain

Si' { predicted  
floodplain


NB

1. This aspect is normally beyond the scope and expertise of pedological survey.

2. Where hydrogeological problems appear evident, these may be indicated but only to emphasize the need for consultation with hydrogeologists.

g.w. D-major ground water discharge areas.

g.w. R-major ground water recharge areas.



### INTERPRETATION

| PROBLEM CLASS | INUNDATION           |     | HYDROGEOLOGICAL PROBLEMS |     | UNFAVOURABLE SLOPES |     |
|---------------|----------------------|-----|--------------------------|-----|---------------------|-----|
| UNLIKELY      | well drained to poor | —   | (unaware of any)         | —   | zone ⊖              | —   |
| POSSIBLE      | Si as above          | Si  | g.w. D                   | Sh  | zone ⊙              | Ss  |
| LIKELY        | Si' as above         | Si' | g.w. R                   | Sh' | zone ⊙'             | Ss' |

# INTEPRETATION

## DWELLINGS

## SOIL PROBLEMS DUE TO EXCAVATION, E

### PROBLEM

Difficult  
Excavations


### TYPES OF PROBLEM CONSIDERED

Hard Materials ——— E

Wet Excavation ——— Ew

### HARD MATERIALS


Stones  
Bedrock  
or Hardpan



### WET EXCAVATION

Seasonal w/table

GRAIN SIZE




## INTERPRETATION

| PROBLEM CLASS | HARD MATERIALS                        |                      | WET EXCAVATION |                     |  |
|---------------|---------------------------------------|----------------------|----------------|---------------------|--|
|               |                                       |                      | w/table        | grain size          |  |
| UNLIKELY      | Other Soils or Bedrock etc. in zone — |                      | —              | zone —<br>PT1 and 2 | —                                      |
| POSSIBLE      | Stones<br>Hardpan<br>Bedrock          | s<br>h<br>r } in PT2 | E              | zone (E)            | zones (E) and (E')<br>and organic soil |
| LIKELY        | Stones<br>Hardpan<br>Bedrock          | s<br>h<br>r } in PT1 | E'             | zone (E')           | zone (E')<br>and organic soil          |

# INTERPRETATION


## DWELLINGS

## SOIL PROBLEMS DUE TO FLOODING, F

| PROBLEM   | TYPES OF FLOODING CONSIDERED   |
|---|--|
|  <p>Seasonal Flooding</p> | <p>Basement flooding ————— Fb</p> <p>Inundation of land ————— Fi</p> |

### BASEMENT FLOODING

### INUNDATION




### INTERPRETATION

| PROBLEM CLASS | BASEMENT FLOODING      |                        |                        | INUNDATION           |     |
|---------------|------------------------|------------------------|------------------------|----------------------|-----|
|               | w/table                | drainage               | Hyd. Cond (K)          |                      |     |
| UNLIKELY      | zone —<br>PT1 and 2    | Well                   | zone —<br>PT1 and 2    | Well drained to poor | —   |
| POSSIBLE      | zone (Fb)              | Imperfect to very poor | zones (Fb) and (Fb)    | Fi as above          | Fi  |
| LIKELY        | zone (Fb)<br>PT1 and 2 | —                      | zone (Fb)<br>PT1 and 2 | Fi' as above         | Fi' |

# INTERPRETATION

## DWELLINGS

# SOIL PROBLEMS DUE TO HEAVE OR UPLIFT, H



### PROBLEM


Cracking of walls  
due to  
differential heave

### TYPES OF HEAVE CONSIDERED

Frost Adhesion ————— Hf  
Expansive Clays ————— Hc  
Expansive Rocks ————— Hr


### FROST ADHESION

Seasonal w/table




### EXPANSIVE SOILS

Seasonal w/table





### EXPANSIVE ROCK

Seasonal w/table



Hr = Shales with Pyrite

### Typical Reactions



## INTERPRETATION

| PROBLEM CLASS | FROST ADHESION               |     | EXPANSIVE CLAY                 |     | EXPANSIVE ROCK             |     |
|---------------|------------------------------|-----|--------------------------------|-----|----------------------------|-----|
|               | w/table                      | —   | w/table zone                   | —   | w/table                    | —   |
| UNLIKELY      | all soils                    | —   | all soils                      | —   | and other soils            | —   |
| POSSIBLE      | w/table zone<br>soils in PT1 | Hf  | w/table in<br>and soils in PT1 | Hc  | w/table in<br>soils in PT1 | Hr  |
| LIKELY        | w/talbe in<br>soils in PT1   | Hf' | w/table in<br>soils in PT1     | Hc' | w/table in<br>soils in PT1 | Hr' |

# INTERPRETATION

## DWELLINGS

# SOIL PROBLEMS DUE TO SETTLEMENT, S



### PROBLEM

Cracking of walls  
due to  
differential settlement


### TYPES OF SETTLEMENT CONSIDERED

Bearing (differential) ——— Sb


Subsidence (organic soils) ——— So

Shrinkage (suction and trees) — St


### BEARING



Q. for dwellings 3  
stories or less



### SHRINKAGE



### INTERPRETATION

| PROBLEM CLASS | BEARING                        |     | SUBSIDENCE                   |     | SHRINKAGE                      |     |
|---------------|--------------------------------|-----|------------------------------|-----|--------------------------------|-----|
| UNLIKELY      | PT 2-4 zone —                  | —   | PT 1-4 (O.M. <2%)            | —   | PT 2-4 zone —                  | —   |
| POSSIBLE      | PT 2-4 zone (Sb)<br>(or other) | Sb  | peaty phase<br>PT 2 O.M. >2% | So  | PT 2-4 zone (St)<br>(or other) | St  |
| LIKELY        | PT 2-4 zone (Sb')              | Sb' | PT 1 organic soil            | So' | PT 2-4 zone (St')              | St' |



LIBRARY / BIBLIOTHEQUE



AGRICULTURE CANADA OTTAWA K1A 0C5

3 9073 00038345 7

